



Acoustical Testing Laboratory

TEST REPORT

for

ICYNENE INC.
6747 Campobello Road
Mississauga, Ontario
Canada L5N 2L7
Andrew Cha / 905-363-4040

Sound Transmission Loss Test
ASTM E 90 - 02
On

1/2" Double layer Gypsum Wall Assembly with
Metal Studs and Icynene Foam Insulation
(Standard Sound Direction)

Page 1 of 4

Report Number: NGC 2004012


Assignment Number: G-194

Specimen Receipt Date: NA


Test Date: 10/15/2004

Report Date: 11/03/2004

Submitted by:


Craig G. Cooper
Test Engineer

Reviewed by:


Robert J. Menchetti
Director

The results reported above apply to specific samples submitted for measurement.
No responsibility is assumed for performance of any other specimen.
This report may not be reproduced except in full, without the written approval of the laboratory.
The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval,
or endorsement by NVLAP or any agency of the U.S. Government.

National
Gypsum
CORPORATION

1650 Military Road • Buffalo, NY 14217-1198
(716)873-9750 • Fax (716)873-9753 • www.ngctestingservices.com

Report Number: NGC 2004012

Test Method: This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements - Designation: E 90 - 02.

Specimen Description: The test specimen was a partition assembly constructed in the 14' W by 9' H test opening with 3-5/8" 25 ga. metal studs, Icynene foam insulation in cavities, 2 layers of 1/2" gypsum wallboard both sides, designated as: 1/2" Gypsum Wall Assembly, metal studs and Icynene Foam Insulation.

Standard direction of sound from Source Room (Room 1) to Receiving Room (Room 2).

The wall system was constructed in the test opening and consisted of:

From Room 1 to Room 2.

- two layers of 1/2" Type C gypsum wallboard. (4.4 PSF)
mounted vertically with staggered seams between layers and attached to studs 24" o.c. with 1" drywall screws inside layer and 12" o.c. with 1-1/2" drywall screws on the outside layer.
- 3-5/8" 25 ga. metal studs 24" o.c. (0.19 PSF)
- 3-5/8" metal channel top and bottom. (0.08 PSF)
- one layer of 2" nominal Icynene spray in place foam insulation. (0.14 PSF)
- two layers of 1/2" Type C gypsum wallboard. (4.4 PSF)
mounted vertically with staggered seams between layers and attached to studs 24" o.c. with 1" drywall screws inside layer and 12" o.c. with 1-1/2" drywall screws on the outside layer.

Total weight of the wall system was 1160 lbs. (9.28 PSF average)

The perimeter of the wall system was sealed with acoustical caulk.

Test sample was applied under direction of client and tested as received.

Cure time for foam insulation was 24 hours minimum.

Test Results: The results of the tests are given on pages 3 and 4.

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.

Sound Transmission Loss Test Data

Page 3 of 4

Per: ASTM E 90 - 02 / ASTM E 413 - 87

No. of test report: NGC2004012

Test Date: 10/15/2004

Size: 11.6 m²

Temperature [°C]: 19.7

Sound Transmission Class STC = 48 dB

Sum of unfavorable deviations: 31.0 dB

Max. unfavorable deviation: 6.0 dB at 125 Hz

| Frequency [Hz] | STL [dB] | L1 [dB] | L2 [dB] | T [s] | Corr. [dB] | u.Dev. [dB] | ΔSTL |
|-------------------|-------------|------------|------------|----------|---------------|----------------|-------|
| 100 | 18 | 100.7 | 85.1 | 2.65 | 2.9 | -- | 0.346 |
| 125 | 26 | 101.3 | 79.1 | 3.12 | 3.6 | 6.0 | 0.640 |
| 160 | 31 | 97.5 | 71.6 | 4.13 | 4.8 | 4.0 | 0.332 |
| 200 | 36 | 99.4 | 69.4 | 4.89 | 5.5 | 2.0 | 0.316 |
| 250 | 35 | 99.9 | 70.2 | 5.10 | 5.7 | 6.0 | 0.200 |
| 315 | 41 | 101.0 | 66.0 | 5.27 | 5.8 | 3.0 | 0.224 |
| 400 | 45 | 102.6 | 62.6 | 4.86 | 5.5 | 2.0 | 0.141 |
| 500 | 46 | 101.1 | 60.1 | 4.71 | 5.3 | 2.0 | 0.224 |
| 630 | 49 | 100.3 | 56.8 | 4.65 | 5.3 | -- | 0.100 |
| 800 | 50 | 100.5 | 55.1 | 4.31 | 5.0 | -- | 0.141 |
| 1000 | 50 | 99.3 | 53.5 | 4.05 | 4.7 | 1.0 | 0.100 |
| 1250 | 52 | 98.1 | 50.3 | 3.69 | 4.3 | -- | 0.100 |
| 1600 | 53 | 97.4 | 48.3 | 3.26 | 3.8 | -- | 0.100 |
| 2000 | 52 | 96.8 | 47.4 | 2.72 | 3.0 | -- | 0.100 |
| 2500 | 48 | 98.1 | 52.9 | 2.42 | 2.5 | 4.0 | 0.100 |
| 3150 | 51 | 98.6 | 49.5 | 2.29 | 2.2 | 1.0 | 0.141 |
| 4000 | 56 | 98.8 | 45.1 | 2.11 | 1.9 | -- | 0.173 |
| 5000 | 58 | 97.5 | 40.4 | 1.89 | 1.4 | -- | 0.200 |

STL = Sound Transmission Loss, dB
 L1 = Source Room Level, dB
 L2 = Receiving Room Level, dB
 T = Reverberation Time, seconds
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.


Sound Transmission Loss Test Data

Per: ASTM E 90 - 02 / ASTM E 413 - 87

No. of test report: NGC2004012
 Test Date: 10/15/2004
 Size: 11.6 m²
 Temperature [°C]: 19.7

Sound Transmission Class STC = 48 dB

| Frequency [Hz] | STL [dB] | ΔSTL |
|----------------|----------|-------|
| 100 | 18 | 0.346 |
| 125 | 26 | 0.640 |
| 160 | 31 | 0.332 |
| 200 | 36 | 0.316 |
| 250 | 35 | 0.200 |
| 315 | 41 | 0.224 |
| 400 | 45 | 0.141 |
| 500 | 46 | 0.224 |
| 630 | 49 | 0.100 |
| 800 | 50 | 0.141 |
| 1000 | 50 | 0.100 |
| 1250 | 52 | 0.100 |
| 1600 | 53 | 0.100 |
| 2000 | 52 | 0.100 |
| 2500 | 48 | 0.100 |
| 3150 | 51 | 0.141 |
| 4000 | 56 | 0.173 |
| 5000 | 58 | 0.200 |



STL = Sound Transmission Loss, dB
 Δ STL = Uncertainty for 95% Confidence Level

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. This report may not be reproduced except in full, without the written approval of the laboratory. The laboratory's accreditation or any of its test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.